



Construction Cost Estimate

607 Concord Avenue · Wilmington, Delaware 19802
ROUGH ORDER OF MAGNITUDE · FULL GUT REHABILITATION WITH COMPLETE MEP REPLACEMENT

TOTAL PROJECT COST — ORDER OF MAGNITUDE

\$292,745 **\$225 / SF**

CONSTRUCTION \$276,174 A/E FEES \$16,570 GROSS AREA 1,300 SF

Project information		Prepared by	
PROJECT	607 Concord Avenue	FIRM	Merge 4 Design LLC
LOCATION	Wilmington, DE 19802	ADDRESS	500 Delaware Ave, Suite 1 #1551
PARCEL	2601530162		Wilmington, DE 19899
JURISDICTION	New Castle County	PROJECT NO.	M2-2026-016
BUILDING	Rowhouse — end unit, corner	ESTIMATE DATE	23 July 2026
CONFIGURATION	2 story + basement + attic	DRAWING BASIS	AD-01 / A-101 / AD-03
GROSS AREA	1,300 SF above grade	DRAWING DATE	28 June 2026
SCOPE	Full gut rehabilitation	ACCURACY	± 20% · AACE Class 4

Project cost control stage				
ROM estimate	Feasibility	Design development	GMP / contract	Closeout
COMPLETE	PENDING	PENDING	PENDING	PENDING

Basis of estimate
This estimate is a rough order of magnitude prepared from the architectural drawing set referenced above. Quantities are derived from plan takeoff and field-verifiable dimensions. Unit rates reflect current Wilmington-area subcontractor pricing for residential rehabilitation of comparable scale and
All mechanical, electrical and plumbing systems are carried as complete replacement, including a 200-amp electrical service upgrade, new gas-fired forced-air heating with cooling, new supply and drain-waste-vent piping, and a new gas water heater.
Exterior scope reflects observed existing conditions including roof replacement to the rafters, porch reconstruction, selective masonry repointing, and re-cladding of the rear wing.
The estimate carries an 8% design and construction contingency and a 10% general contractor overhead and profit allowance. Architecture and engineering fees are shown separately at 6% of construction cost.
Prepared for budgeting, financing and feasibility purposes. This is not a bid, a guaranteed maximum price, or an offer to perform work. Competitive contractor pricing should be obtained prior to any funding commitment or construction contract.



Cost summary

Direct construction cost	52 line items • 10 divisions	\$232,470
Design & construction contingency	8% of direct cost	\$18,598
General contractor overhead & profit	10%	\$25,107
Total construction cost	Hard cost	\$276,174
Architecture & engineering fees	6% of construction	\$16,570
TOTAL PROJECT COST	Order of magnitude	\$292,745

Cost metrics

GROSS FLOOR AREA	DIRECT COST / SF	CONSTRUCTION / SF	TOTAL PROJECT / SF
1,300 SF	\$178.82	\$212.44	\$225.19

Cost distribution by division

Division	Subtotal	Share of direct
01 GENERAL CONDITIONS	\$9,200	4.0%
02 DEMOLITION	\$20,050	8.6%
03 FOUNDATIONS & STRUCTURE	\$14,300	6.2%
04 EXTERIOR ENVELOPE	\$42,450	18.3%
05 INTERIOR CONSTRUCTION	\$19,520	8.4%
06 FINISHES	\$21,300	9.2%
07 KITCHEN & BATHS	\$35,600	15.3%
08 PLUMBING	\$21,200	9.1%
09 HVAC	\$22,650	9.7%
10 ELECTRICAL	\$26,200	11.3%
Direct construction cost	\$232,470	100.0%

Existing condition observations

FRONT ELEVATION	Two-story brick rowhouse with attic dormer. Arched masonry window surrounds intact. Full-width covered porch. Entry door boarded in current imagery — structure vacant and secured.
CORNER / SIDE	End-unit condition exposes the full side elevation. Stone foundation shows moisture staining and efflorescence at grade. Basement openings boarded.
REAR WING	Addition clad in vinyl siding, weathered and deteriorated. Re-clad carried in Division 04.
ROOF	Existing roof aged beyond serviceable life. Full strip to rafters carried in Division 02.
HAZARDOUS MATERIALS	Structure predates 1978. Lead paint and asbestos presumed present. Survey and abatement excluded — see Exclusions, page 4.



Construction cost detail — full quantity and rate buildup

Scope item	CSI ref	Qty	Unit	Unit cost	Line total	% of dir.
01 GENERAL CONDITIONS						
Temporary protection, site safety, dumpsters, cleanup	DIV 01-TF	1	LS	\$4,500.00	\$4,500	1.9%
Permits & inspections — New Castle County	DIV 01-PM	1	LS	\$3,500.00	\$3,500	1.5%
Final clean	DIV 01-FC	1	LS	\$1,200.00	\$1,200	0.5%
Division subtotal					\$9,200	
02 DEMOLITION						
Selective demo — windows, exterior doors, sidelights	DIV 02-DI	1	LS	\$3,500.00	\$3,500	1.5%
Remove exterior brick wall to roof level	DIV 02-DE	1	LS	\$4,200.00	\$4,200	1.8%
Remove load-bearing structural wall (interior)	DIV 02-DS	1	LS	\$2,800.00	\$2,800	1.2%
Roof demolition — strip to rafters	DIV 02-DR	1,300	SF	\$2.50	\$3,250	1.4%
Floor sheathing removal / porch decking demo	DIV 02-DF	1	LS	\$1,800.00	\$1,800	0.8%
MEP demolition — remove systems back to mains	DIV 02-DM	1	LS	\$4,500.00	\$4,500	1.9%
Division subtotal					\$20,050	
03 FOUNDATIONS & STRUCTURE						
Repair & parge foundation — front and side elevations	DIV 03-CR	1	LS	\$2,800.00	\$2,800	1.2%
Repair basement slab — patch / limited pour	DIV 03-CS	1	LS	\$1,800.00	\$1,800	0.8%
New LVL beam & posts at each end	DIV 06-SF	1	LS	\$6,500.00	\$6,500	2.8%
New 2x10 floor joists	DIV 06-FJ	5	EA	\$640.00	\$3,200	1.4%
Division subtotal					\$14,300	
04 EXTERIOR ENVELOPE						
Asphalt shingle roof — main pitched areas	DIV 07-RS	1,300	SF	\$7.50	\$9,750	4.2%
Low-slope rubber membrane roof — porch / flat area	DIV 07-RM	1	LS	\$4,800.00	\$4,800	2.1%
Porch rebuild — decking, vinyl railings, steps	DIV 06-PR	1	LS	\$5,600.00	\$5,600	2.4%
Exterior entry door with sidelights — front	DIV 08-DE	1	EA	\$2,800.00	\$2,800	1.2%
Exterior rear door	DIV 08-DR	1	EA	\$1,800.00	\$1,800	0.8%
Replacement windows — match existing profile	DIV 08-WD	8	EA	\$950.00	\$7,600	3.3%
Masonry infill at basement window openings	DIV 04-MI	3	EA	\$800.00	\$2,400	1.0%
Rear wing re-clad — fiber cement siding	DIV 07-SD	1	LS	\$4,500.00	\$4,500	1.9%
Brick repointing — spot tuckpointing	DIV 04-RP	1	LS	\$3,200.00	\$3,200	1.4%
Division subtotal					\$42,450	
05 INTERIOR CONSTRUCTION						
Gypsum board — walls and ceilings, all levels	DIV 09-GB	2,600	SF	\$4.20	\$10,920	4.7%
Interior doors per schedule	DIV 08-DI	8	EA	\$550.00	\$4,400	1.9%
Closet shelving / linen storage	DIV 06-MW	1	LS	\$1,800.00	\$1,800	0.8%
Stair repair and refinish	DIV 06-ST	1	LS	\$2,400.00	\$2,400	1.0%
Division subtotal					\$19,520	
06 FINISHES						
Vinyl plank flooring on T&G plywood underlayment	DIV 09-FV	800	SF	\$6.50	\$5,200	2.2%
Carpet — bedrooms	DIV 09-FC	400	SF	\$4.00	\$1,600	0.7%
Ceramic tile — bathrooms and kitchen	DIV 09-FT	220	SF	\$9.00	\$1,980	0.9%
Paint — walls, ceilings, trim	DIV 09-PT	2,600	SF	\$3.20	\$8,320	3.6%
Trim and millwork — base, casing	DIV 06-TM	1	LS	\$4,200.00	\$4,200	1.8%
Division subtotal					\$21,300	

Construction cost detail — full quantity and rate buildup						
Scope item	CSI ref	Qty	Unit	Unit cost	Line total	% of dir.
07 KITCHEN & BATHS						
Kitchen — cabinets, countertops, sink	DIV 12-KC	1	LS	\$12,000.00	\$12,000	5.2%
Range and hood	DIV 11-AP	1	EA	\$1,800.00	\$1,800	0.8%
Full bath — vanity, toilet, tub, tile	DIV 12-BF	1	EA	\$8,500.00	\$8,500	3.7%
Powder room — vanity and toilet	DIV 12-BP	1	EA	\$3,800.00	\$3,800	1.6%
Master bath — vanity, toilet, tub/shower, tile	DIV 12-BM	1	EA	\$9,500.00	\$9,500	4.1%
Division subtotal					\$35,600	
08 PLUMBING						
Gas hot water heater	DIV 22-WH	1	EA	\$2,200.00	\$2,200	0.9%
PEX supply piping — full distribution	DIV 22-SP	1	LS	\$6,500.00	\$6,500	2.8%
PVC drain, waste and vent system	DIV 22-DV	1	LS	\$8,500.00	\$8,500	3.7%
Fixture rough-in	DIV 22-RI	1	LS	\$2,800.00	\$2,800	1.2%
Sump pump — replace and reconnect	DIV 22-SU	1	EA	\$1,200.00	\$1,200	0.5%
Division subtotal					\$21,200	
09 HVAC						
Gas furnace — forced air	DIV 23-FA	1	EA	\$5,500.00	\$5,500	2.4%
Condenser and evaporator coil	DIV 23-AC	1	EA	\$4,800.00	\$4,800	2.1%
Ductwork — supply and return, all floors	DIV 23-DW	1	LS	\$9,500.00	\$9,500	4.1%
Registers, grilles, programmable thermostat	DIV 23-TR	1	LS	\$1,800.00	\$1,800	0.8%
Bathroom exhaust fans	DIV 23-EF	3	EA	\$350.00	\$1,050	0.5%
Division subtotal					\$22,650	
10 ELECTRICAL						
200A panel — service upgrade	DIV 26-SV	1	EA	\$4,500.00	\$4,500	1.9%
Branch wiring — circuits throughout	DIV 26-BW	1	LS	\$12,000.00	\$12,000	5.2%
Outlets, switches, devices	DIV 26-DV	1	LS	\$3,200.00	\$3,200	1.4%
Lighting fixtures — allowance	DIV 26-LT	1	LS	\$4,500.00	\$4,500	1.9%
Smoke and CO detectors per code	DIV 26-SD	1	LS	\$800.00	\$800	0.3%
Kitchen appliance circuits	DIV 26-AC	1	LS	\$1,200.00	\$1,200	0.5%
Division subtotal					\$26,200	
TOTAL DIRECT CONSTRUCTION COST					\$232,470	

Exclusions

- Hazardous materials survey, abatement or disposal (lead, asbestos) — structure predates 1978
- Structural engineering design and stamped calculations
- Site work, landscaping, driveway, fencing and utility service laterals
- Appliances beyond range and hood; window treatments; furnishings
- Owner-directed upgrades above stated allowances
- Escalation beyond estimate date; permit expediting; financing and carrying costs